

15-109-20669-00-00

4-061162

6-18

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-109-20,669  
40'E.of  
SW NW SE /4 SEC. 11, 11 S, 34 W  
1650 feet from S section line  
2270 feet from E section line

Operator license# 5003

Lease: Bertrand B Well # 1-11

Operator: McCoy Petroleum Corporation

County: Logan 154.87

Address: 3017 N. Cypress  
Wichita, Kansas 67226

Well total depth 4765 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 252 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Mallard JV Inc. License# 4958

Address: 2080 E. Kansas Avenue, McPherson, Kansas 67460

Company to plug at: Hour: 7:30 P.M. Day: 18 Month: June Year: 1998

Plugging proposal received from: Carol Nickel

Company: Mallard JV Inc. Phone: 316-241-4640

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour 10:30 P.M., Day: 18, Month: June, Year: 1998

Actual plugging report:

1st. Plug at 2670' w/25 sxs. Anhydrite 2647' - 2674'.

2nd. Plug at 1575' w/100 sxs. Dakota 1268' - 1568'.

3rd. Plug at 305' w/40 sxs. Surface pipe - 252'.

4th. Plug at 40' w/10 sxs.

Rathole with 15 sxs.

Mousehole with 10 sxs.

6-23-1998


Remarks: Halliburton Cementing.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: 3168 GL

I did [ ] / did not [ X ] observe the plugging.

  
DH (agent)  
Form CP-2/3

INVOICED  
DATE 6-24-98  
50817