

15-09-20541-00-00

4-090502

11-6

15W  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-109-20,541

NE NW SW /4 SEC. 11, 11 S, 34 W  
2310 feet from S section line  
990 feet from W section line

Operator license# 06113

Lease Bertrand well #1-11

Operator: Landmark Oil Exploration, Inc.

County Logan

Address: 250 N. Water  
Suite 308  
Wichita, Kansas 67202

Well total depth 4770 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 361 feet

155.03

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Murfin Drilling Company, Inc. License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 5 Month: November Year: 92

Plugging proposal received from: Keith VanPelt

Company: Murfin Drilling Company, Inc. Phone:     -    

Were: Order 190 sks. 60/40 posmix - 6% gel.  
Spot all plugs through drill stem with heavy mud between  
all plugs.

Plugging Proposal Received by: Ed Schumacher

Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 4:15P.M., Day: 6, Month: November, Year: 92

Actual plugging report:

1st. plug @ 2670' w/25 sks. cement.  
2nd. plug @ 1590' w/100 sks. cement.  
3rd. plug @ 410' w/40 sks. cement.  
4th. plug @ 40' w/10 sks. cement.  
15 sks. cement in Rathole.  
Arbuckle - No - Anhydrite 2655' - 2680'

RECEIVED  
STATE CORPORATION COMMISSION  
12-7-1992  
DEC 7 1992

Remarks:

Condition of casing(in hole): GOOD      BAD      Anhy. plug: YES X NO       
Bottom plug(in place): YES     , CALC     , NO X Dakota plug: YES X, NO       
Plugged through TUBING     , CASING     . Elevation: 3190 GL

12-7-1992  
DEC 7 1992

I did      / did not [ X ] observe the plugging.

Ed Schumacher

DATE 12-9-92  
INV. NO. 37024

(agent)

Form CP-2/3