

15-109-20623-00-00

4-020094

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API number: 15-109-20,623-0000

4-26

C SE SW /4 SEC. 11 , 11 S, 34 W
660 feet from S section line
3300 feet from E section line

Operator license# 06113

Lease: Bertrand "A" Well # 1-11

Operator: Landmark Energy Exploration, Inc.
Address: / Vess Oil
1861 N. Rock Road, Suite 205
Wichita, Kansas 67206

County: Logan 154.70
Well total depth 4760 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 382 feet

Aband. oil well _____, Gas well _____, Input well _____, SWD _____, D & A X

Plugging contractor: L. D. Drilling, Inc. License# 06039

Address: R.R. 1, Box 183B, West 10th Street, Great Bend KS 67530

Company to plug at: Hour: _____ Day: 26 Month: April Year: 1996

Plugging proposal received from: Greg Davidson

Company: L. D. Drilling Phone: 316 793 3051

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2650 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1570 feet with 100 sacks

3rd plug @ 430 feet with 40 sacks

4th plug @ 40 feet with 10 sacks

RECEIVED
KANSAS CORP COMM
APR 31 4 31 PM '96

Plugging Proposal Received by: Ken Kuhn

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 10:00 PM, Day: 26, Month: April, Year: 1996

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2.0 sx celloflake or flowcel.

Remarks: Allied Cementing performed the cement job.

Condition of casing(in hole): GOOD X BAD _____ Anhy.plug: YES X NO _____

Bottom plug(in place): YES X, CALC _____, NO _____ Dakota plug: YES X, NO _____

Plugged through TUBING _____, CASING X Elevation: 3168 GL

INVOICED
I did not [X] observe the plugging.

[Signature]
(agent)

DATE MAY 06 1996

INV. NO. 45522