

15-109-20658-00-00

4-070082

10-21-97

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-109-20,658

SE NW NW /4 SEC. 16, 11 S, 34 W  
4290 feet from S section line  
4290 feet from E section line

Operator license# 5135

Lease: Gordon Well # 1

Operator: John O. Farmer

County: Logan 156.98

Address: P.O. Box 352  
Russell, Kansas 67665

Well total depth 4830 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 258e feet

ABAND. oil well, Gas well, Input well, SWD., D&A X

Plugging contractor: Abercrombie RTD, Inc. License# 5363

Address: 150 N. Main - Suite #801 - Wichita, Kansas 67202-1383

Company to plug at: Hour: 7:15 P.M. Day: 21 Month: October Year: 1997

Plugging proposal received from: Company Man

Company: Abercrombie RTD, Inc. Phone: -

Were: Ordered 190 sxs 60/40 pozmix - 6% gel - 1/4# floseal per sack.  
Spot plug through drill pipe with heavy drilling mud between all plugs.  
RTD 4830', 8 5/8" set at 258'.

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 9:45 P.M., Day: 21, Month: October Year: 1997

Actual plugging report:  
1st. Plug at 2700' w/25 sxs. - Anhydrite 2690' - 2718'.  
2nd. Plug at 1606' w/100 sxs. - Dakota Base.  
3rd. Plug at 308' w/40 sxs. - Surface pipe 258' + 50' with 8 5/8" wiper plug.  
No Arbuckle cut.  
15 sxs in rathole.

Remarks:  
Condition of casing(in hole): GOOD BAD  
Bottom plug(in place): YES, CALC, NO  
Plugged through TUBING, CASING.  
Anhy.plug: YES X NO  
Dakota plug: YES X, NO  
Elevation: GL

I did[ ] / did not[ X ] observe the plugging.

STATE OF KANSAS  
1-28-1998  
JAN 20 1998  
Richard Williams  
(agent)

Form CP-2/3

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 1-29-98

INV. NO. 50011