

4-020077

TO: 10-31  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API number: 15-109-20,597-0000

NE NE SE /4 SEC. 23, 11 S, 34 W  
2310 feet from S section line  
330 feet from E section line

Operator license# 05030

Lease: Avila Well # 1-23

Operator: Vess Oil Corporation  
Address: 8100 E. 22nd St. North  
Bldg. 300  
Wichita, KS 67226

County: Logan 155.35  
Well total depth 4780 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8% Inch @ 319 feet

Aband. oil well \_\_\_\_\_, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A X

Plugging contractor: L. D. Drilling, Inc. License# 06039

Address: R.R. 1, Box 183B, West 10th. St., Great Bend KS 67530

Company to plug at: Hour: \_\_\_\_\_ Day: 31 Month: October Year: 1995

Plugging proposal received from: Greg Davidson

Company: L. D. Drilling, Inc. Phone: 316 793 3051

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2645 feet with 25 sacks Rat hole: 15 sacks  
2nd plug @ 1560 feet with 100 sacks  
3rd plug @ 370 feet with 40 sacks  
4th plug @ 40 feet with 10 sacks

Plugging Proposal Received by: Ken Kuhn

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 10:45 PM, Day: 31, Month: October, Year: 1995

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2.0 sx celloflake or flowcel.

Remarks: Allied Cementing perfomed the cement job.

Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Any plug: YES X NO \_\_\_\_\_

Bottom plug(in place): YES X, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_

Plugged through TUBING \_\_\_\_\_, CASING X Elevation: 3162 GL

INVOICED did not [ X ] observe the plugging.

Ken Kuhn  
(agent)  
Form CP-2/3

DATE 11-13-95  
INVL NO. 44009