

2-12

4-041881

15-109-20643-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-109-20,643

NE SW NW /4 SEC. 14, 11 S, 34 W
1650 feet from N section line
990 feet from W section line

Operator license# 5135

Lease: Smith Well # 1

Operator: John O. Farmer, Inc.

County: Logan 155.67

Address: P.O. Box 352
Russell, Kansas 67665

Well total depth 4790 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 267 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Abercrombie RTD, Inc. License# 30684

Address:

Company to plug at: Hour: A.M. Day: 12 Month: February Year 1997

Plugging proposal received from: Tony Martin

Company: Abercrombie RTD, Inc. Phone:

Were: Order 190 sxs 60/40 pozmix with 6% gel - 1/4# floseal per sack.
Spot plug through drill pipe with heavy mud between all plugs.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 3:30 P.M., Day: 12, Month: February, Year: 1997

Actual plugging report:
1st. plug at 2674' w/25 sxs.
2nd. plug at 1575' w/100 sxs.
3rd. plug at 320' w/40 sxs.
4th. plug at 40' w/10 sxs.
15 sxs in rathole.

RECEIVED
KANSAS CORP COMM
1997 FEB 20 11:01

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X NO
Plugged through TUBING, CASING. Elevation: 3184 GL

I did [] / did not [X] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED

DATE FEB 21 1997

INV. NO. 47648

2-12