

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-109-20,640-00-00

15-109-20640-00-00

LEASE NAME SOUCIE "A"

TYPE OR PRINT

WELL NUMBER #1-22

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1320 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 22 TWP. 11s RGE. 33w (E) or (W)

COUNTY Logan

Date Well Completed 2/18/97

Plugging Commenced 2/17/97

Plugging Completed 2/18/97

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 3017 N. Cypress, Wichita, KS 67226-4003

PHONE# (316) 636-2737 OPERATORS LICENSE NO. 5003

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/18/97 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, Is well log attached? _____

RECEIVED
KANSAS CORPORATION COMMISSION

Producing Formation None Depth to Top _____ Bottom T.D. 4768'

Show depth and thickness of all water, oil and gas formations.

APR 11 1997
4-11-1997
CONSERVATION DIVISION
WICHITA, KS

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface		0	262'	8 5/8"	262'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

D&A using 60/40 Pozmix, 6%Gel, 1/4# Flocele: 1st plug at 2660' with 25 sacks, 2nd plug at 1650' with 100 sacks, 3rd plug at 315' with 40 sacks, 4th plug at 40' with 10 sacks, Rathole with 15 sacks, Mousehole with 10 sacks. Plugging completed at 12:30a.m. on 2/18/97.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sweetman Drilling, Inc. License No. 5658

Address 3017 N. Cypress, Wichita, KS 67226-4003

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

Brent B. Reinhardt (Employee of Operator) ~~xxxxxxx~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Brent B Reinhardt

(Address) 3017 N. Cypress, Wichita, KS 67226

SUBSCRIBED AND SWORN TO before me this 5th day of March, 1997

Deborah Ann Paulus
Notary Public

My Commission Expires: January 8, 2000

