

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

#4 API NUMBER 15 - 109-20,457-00-00

15-109-20457-00-00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Ehrlich

WELL NUMBER 1

4290 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 25 TWP. 11 RGE. 33 (E or W)

COUNTY Logan

LEASE OPERATOR National Petroleum Reserves, Inc.

ADDRESS 260 N. Rock Rd., Ste. 215, Wichita, KS 67206

PHONE# (316) 681-3515 OPERATORS LICENSE NO. 9482

Character of Well D & A Dry

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 5-6-88

Plugging Commenced 5-6-88

Plugging Completed 5-6-88

The plugging proposal was approved on 4-29-88 (date)

by Dave Wann (KCC District Agent's Name).

Is ACO-1 filed? operator ^{Will be by yes} If not, Is well log attached? Yes NONE RUN

Producing Formation TO Top Bottom T.D. 4695'

Show depth and thickness of water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	Size	Put in	Pulled out
		From			
		CONSERVATION DIVISION			
		Wichita, Kansas			

RECEIVED
AUG 5 1988
8-5-1988
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
1st plug at 2615' w/25 sx thru drill pipe
2nd plug at 1600' w/100 sx thru drill pipe
3rd plug at 430' w/40 sx thru drill pipe
4th plug at 40' w/10 sx w/plug
(If additional description is necessary, use BACK of this form.)

Name or Plugging Contractor Lobo Drilling Company License No. 5864

Address P. O. Box 877, Great Bend, KS 67530


STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors
(Address) P. O. Box 877, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 12 day of May, 19 88

Dorothy M Hague
Notary Public



Commission Expires: _____

DRILLERS WELL LOG

DATE COMMENCED: April 27, 1988

DATE COMPLETED: May 6, 1988

National Petroleum Reserves, Inc.
EHRlich #1
SW NW NE
Sec. 25-11-33W
Logan County, KS

0 - 162'	Sand & Clay
162 - 1940'	Shale
1940 - 2307'	Shale & Lime
2307 - 2612'	Lime & Shale
2612 - 2638'	Anhydrite
2638 - 2645'	Lime
2645 - 3662'	Lime & Shale
3662 - 3838'	Lime
3838 - 4193'	Lime & Shale
4193 - 4194'	Lime
4194 - 4440'	Lime & Shale
4440 - 4695'	Lime
4695'	RTD

Surface Pipe: Set used 8 5/8" pipe, 24# at 387' with 220 sx 60/40 Poz, 3% C.C., 2% Gel.

RECEIVED
STATE CORPORATION COMMISSION
8-5-1988
AUG - 5 1988

CONSERVATION DIVISION
Wichita, Kansas

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors
Ervin Neighbors

SUBSCRIBED AND SWORN to before me this 12 day of May, 1988.

Dorothy M Hague
Notary Public

