

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Logan SEC. 25 TWP. 11s RGE. 33w E/W
 Location as in quarters or footage from lines:
 NW NW NE

Locate Well
 correctly on above
 Section Platt.

Lease Owner K & E Petroleum, Inc.
 Lease Name Ehrlich #1 Well No. _____
 Office Address 100 S. Main, Suite 300, Hardage Center, Wichita, Ks
 Character of Well (Completed as Oil, Gas or Dry Hole): 67202
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 4/21/83
 Plugging completed 4/27/83
 Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4780'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	348'	none
				4 1/2"	4737.68'	1441'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Pumped bottom with 60 sacks cement, 100 bbl. fresh water, pumped cement, turned
 plug loose, well went on vacuum. Plug stopped at 4480'. Used 50 more sacks
 cement & another plug. Pump bottom again, run plug down, went on vacuum again.
 Stopped plug at 3500'. Tagged plug at 3510'. Shot pipe at 3448', 2881', 2640',
 2439' 2197', 2003', 1797', 1675', 1555', & 1434'. Pulled 36 joints. Plugged
 well with 2 hulls, 17 gel, 100 cement, 23 gel, 8 5/8 plug & 70 cement.

Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
 Box 347, Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of May, 19 83



My Commission expires: _____

Irene Hoover
 Notary Public.

RECEIVED
 STATE CORPORATION COMMISSION
 5-9-1983
 MAY 09 1983

RECEIVED
NOV 19 1981

15-109-20184-00-00

CONTRACTORS WELL LOG

OPERATOR:	K & E Petroleum, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	EHRlich #1
LOCATION:	NW NW NE, Sec. 25-11S-33W Logan County, Kansas
SPUD DATE:	10/16/81
COMPLETION DATE:	10/26/81

0	350	Surface
350	2610	Shale & Sand
2610	2674	Anhydrite
2674	3024	Shale & Sand
3024	3725	Shale
3725	3940	Shale with Sand
3940	4165	Lime & Shale
4165	4460	Lime
4460	4632	Lime & Shale
4632	4780	Lime
	4780	Rotary Total Depth

Spud hole @ 4:30 p.m., 10/16/81. Drilled 250' of a 12½" hole. Ran 9 joints of 8 5/8" 20# casing set @ 348' and cemented with 250 sx. 60-40 posmix, 3% c.c. 2% gel. Plug was down @ 11:30 p.m., 10/16/81. Cement did circulate.

4780' TD. Ran 20 joints of 4½" 10½# casing, 102 joints 4½" 10½# casing, set @ 4729'. Ran 30 barrels Chemical Flush, 35 sx. 50-50 posmix, 4% gel, 4# Gilsinit per sack, 1½# D-29 per sack. Plug was down @ 12:15 p.m., 10/26/81.

SAMPLE TOPS:

Anhydrite	2610'
B/Anhydrite	2637'

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the EHRlich #1, NW NW NE, Sec. 25-11S-33W, Logan County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state, as of this 3rd day of November, 1981.

RECEIVED

STATE CORPORATION COMMISSION

FEB 18 1983

2-18-1983

CONSERVATION DIVISION
Wichita, Kansas

Elizabeth G. Terry
Elizabeth G. Terry
NOTARY PUBLIC

my commission expires 7-13-85

