

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: C&E Oil
Address: 422 Elm Moline, Ks 67353
Phone: (620) 647-3601 Operator License #: 3591
Type of Well: Oil Docket #: NA
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 12/30/08 (Date)
by: DeWayne Simms (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Arbuckle Depth to Top: 2280 Bottom: 2284.4 T.D. 2284.4
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-049-20709-00-00
Lease Name: Vejal
Well Number: #1
Spot Location (QQQQ): SE-SE-SW
NE NE NW
330 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 35 Twp. 31 S. R. 10 East West
County: Elk
Date Well Completed: 08/25/80
Plugging Commenced: 12/30/08
Plugging Completed: 12/30/08

*KCC District Agent
Per [Signature]*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
surface		0	211	8 5/8	211	none
Arbuckle	oil	0	2280	4 1/2	2280	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Cast iron bridge plug set 1908, perf well at 1000 ft, 2 shots, perf well at 500, 2 shots, run tubing to 1906 pump 10 sacks of cement, pull tubing to 1100 ft, pump gel spacer 100#, pull tubing to 900 ft, pump 10 sackds to cement, pull tubing to 600 ft, pump gel spacer 100#, pull tubing to 500 ft, pump 135 sacks cement circulate to top

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: C&E Oil License #: 3591
Address: 422 Elm Moline Ks 67353
Name of Party Responsible for Plugging Fees: C&E Oil
State of Ks County, Elk, ss.

JAN 29 2009

CONSERVATION DIVISION
WICHITA, KS

Ed Triboulet (Employee of Operator) or Operator on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 422 Elm Moline Ks 67353

SUBSCRIBED and SWORN TO before me this 26th day of January, 2009
Cindy L. Slinkard My Commission Expires: _____
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas

CINDY L. SLINKARD
Notary Public - State of Kansas
My Apt. Expires 1-9-2011

[Handwritten mark]