

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: C&E Oil  
Address: 422 Elm Moline, Ks 67353  
Phone: (620) 647-3601 Operator License #: 3591  
Type of Well: oil Docket #: NA  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)* *(If SWD or ENHR)*  
The plugging proposal was approved on: 12/31/08 (Date)  
by: DeWayne Simms (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Mississippi Depth to Top: 2174 Bottom: 2181.5 T.D. 2181.5  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-049-20152-00-00  
Lease Name: Adaline Wilson  
Well Number: #1 Adaline Wilson *KCCPT*  
Spot Location (QQQQ): SE - SE - SW  
330 Feet from  North /  South Section Line  
2150 Feet from  East /  West Section Line  
Sec. 7 Twp. 31 S. R. 10  East  West  
County: Elk  
Date Well Completed: 11/30/71  
Plugging Commenced: 12/31/08  
Plugging Completed: 12/31/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
surface		0	99 ft	8 5/8	99 ft	none
Mississippi	oil	2174.5	2181	4 1/2	2174.5	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf well at a 1000 ft, 2 shots to perf well at 500 ft 2 shots, run tubing to 2181 put bottom plug of 10 sacks cement, pull tubing to 1100 ft, pump gel spacer of 100# then pull tubing up 900 ft, pump 10 sacks of cement then pull tubing to 600 ft, pump 100# gel spacer pull tubing up to 500 ft pump 180 sacks of cement circulated to top

RECEIVED  
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: C&E Oil License #: 3591  
Address: 422 Elm Moline Ks 67353  
Name of Party Responsible for Plugging Fees: C&E Oil  
State of Ks County, Elk, ss.

JAN 29 2009

CONSERVATION DIVISION  
WICHITA, KS

Ed Triboulet (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Ed Triboulet  
(Address) 422 Elm Moline Ks 67353

SUBSCRIBED and SWORN TO before me this 26th day of January, 2009

Cindy L. Slinkard  
Notary Public My Commission Expires: \_\_\_\_\_

GINDY L. SLINKARD  
Notary Public - State of Kansas  
My Appt. Expires 1-9-2011

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*PA*