

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: McCoy Petroleum Corporation
Address: 8080 E. Central, Suite #300, Wichita, KS 67206-2366
Phone: 316-636-2737 Operator License # 5003

API Number 15- 039-21084 - 00 - 00
Lease Name: BROWN "E" #1-3Z KCCP/A
Well Number: #1-32

Type of Well: D&A Docket #:
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 1/25/09 (Date)
by: Rich Williams (KCC District Agent's Name)

Spot Location (QQQQ): S2 SE NW
2210 Feet from [X] North / [ ] South Section Line
1980 Feet from [ ] East / [X] West Section Line
Sec 32 Twp 4 S. Rng. 30 [ ] East [X] West
County: Decatur

Is ACO-1 filed? [X] Yes [ ] No If not, is well log attached? [ ] Yes [X] No
Producing Formation(s): List All (If needed attach another sheet)

None Depth to Top: Bottom: T.D.
Depth to Top: Bottom: T.D.
Depth to Top: Bottom: T.D.

Date Well Completed: 1/25/09
Plugging Commenced: 1/25/09
Plugging Completed: 1/26/09

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: 8 5/8", 220', None.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1/25/09: Plugged with 220 sacks of 60/40 pozmix with 4% gel and 1/4#/sack flocelle as follows: 25 sks @ 2618', 100 sks @ 1900', 40 sks @ 270', 10 sks @ 0-40', 30 sks in Rathole and 15 sks in Mousehole.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606
Address: 250 N. Water Street, Suite #300, Wichita, KS 67202
Name of Party Responsible for Plugging Fees: McCoy Petroleum Corporation
State of Kansas County, Sedgwick, ss.

RECEIVED
KANSAS CORPORATION COM
FEB 04 2009

Scott Hampel - Vice President, Production (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

BRENT B. REINHARDT
Notary Public - State of Kansas
My Appt. Expires 12/7/2011

(Signature) Scott Hampel
(Address) 8080 E. Central, Suite #300, Wichita, KS 67206-2366

SUBSCRIBED and SWORN TO before me this 2nd day of February 20 09
Brent B. Reinhardt My Commission Expires: 12/7/2011
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten initials/signature.