

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Farmer, John O., Inc.  
Address: 370 W ichita Ave, PO Box 352, Russell KS 67665  
Phone: (785 ) 483 - 3144 Operator License #: 5135  
Type of Well: D & A Docket #: None  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
The plugging proposal was approved on: 12/1/08 (Date)  
by: Bruce Bayse (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 065-23512-00-00  
Lease Name: F & A Unit  
Well Number: #1  
Spot Location (QQQQ): SE - SE - SE - SW  
128 Feet from  North /  South Section Line  
2570 Feet from  East /  West Section Line  
Sec. 27 Twp. 9 S. R. 22  East  West  
County: Graham  
Date Well Completed: 12/3/08  
Plugging Commenced: 12/4/08 @ 12:00 pm  
Plugging Completed: 12/4/08 @ 4:00 pm

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	217'	8 5/8	217'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Commenced Plugging 12/4/08 @ 12:00 pm, 1st stage 25sx @ 3978', 2nd stage 25sx @ 1880', 3rd stage 100sx @ 1120', 4th stage 40sx @ 270', 5th stage <sup>10</sup> sx @ 40', 30sx in rathole. Total of 230 sx of 60/40 poz,- 4% gel,- 1/4# per sx flo-seal. Drilling mud was placed between stages. Plug was complete 12/4/08 @ 4:00 pm, by Allied Cementing

Name of Plugging Contractor: WW Drilling, LLC License #: 33575  
Address: 233 S 4th, PO Box 307, Wakeeney KS 67672

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 03 2009  
CONSERVATION DIVISION  
WICHITA, KS


Name of Party Responsible for Plugging Fees: Farmer John, O., Inc.  
State of Kansas County, Russell, ss.

John O. Farmer IV (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) John O. Farmer IV  
(Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED and SWORN TO before me this 2nd day of February, 20 09

My Commission Expires: \_\_\_\_\_  
Notary Public  
Margaret A. Schulte



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten initials/signature.