

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Pickrell Drilling Company, Inc.
Address: 100 S Main, Suite 505, Wichita, KS 67202
Phone: (316) 262-8427 Operator License #: 5123
Type of Well: Oil/Gas KCCPTPR 0213 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Steve Durrant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: ⁰³³⁻15-03-21294-00-00
Lease Name: Bird N
Well Number: 1
Spot Location (QQQQ): _____ - E/2 - SW - SW
660 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 3 Twp. 32 S. R. 19 East West
County: Comanche
Date Well Completed: 1-16-02
Plugging Commenced: 1-28-09
Plugging Completed: 1-30-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	686	
				4 1/2	5420	3600

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Raised pole, blew gas off casing, pumped 50 sacks, 200# hulls down 4 1/2" casing, displaced with 70 bbls, max pressure 300 psi, shut in 150 psi, dug cellar, unpacked casing head, set floor, tagged cement at 4650', pulled slips, had 28" stretch, ripped casing at 4020', worked casing, ripped casing at 3810', worked casing, ripped casing at 3600', worked pipe free, set casing on bottom, pulled casing up to 1080', pumped 15 gel, 50 sacks, 100# hulls, pulled to 720', pumped 40 sacks, 100# hulls, pulled to 40', pumped 20 sacks to surface, tore down floor and rig, cleaned up location.

RECEIVED
KANSAS CORPORATION COMMISSION


Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 190 US Highway 56, Ellinwood, KS 67524

FEB 05 2009

Name of Party Responsible for Plugging Fees: Pickrell Drilling Company, Inc
State of Kansas County, Sedgwick, ss.

CONSERVATION DIVISION
WICHITA, KS

Jack Gurley (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Jack Gurley
(Address) 100 S. Main, Suite 505 Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 4th day of February, 2009
Karen A. Mans McGee My Commission Expires: 6-23-2012
Notary Public
Karen A. Mans McGee

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]