

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: EOG Resources, Inc.  
Address: 3817 NW Expressway, Suite 500 Oklahoma City, OK 73112-1483  
Phone: (405) 246-3126 3100 Operator License #: 5278  
Type of Well: D&A FEEDDH KCCPRT Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 1/15/2009 (Date)  
by: Steve Durant (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Mississippian Depth to Top: 4563' Bottom: 4569' T.D. 6500'  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 189-22619 - 0000  
Lease Name: Caliber 12  
Well Number: # 1 SW SW  
Spot Location (QQQQ): NE - NE - NE - NW  
1700 Feet from  North /  South Section Line  
1860 Feet from  East /  West Section Line  
Sec. 12 Twp. 32 S. R. 36  East  West  
County: Stevens  
Date Well Completed: 10/20/2007 11-26-07  
Plugging Commenced: 1/21/2009  
Plugging Completed: 1/22/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	1610'	8 5/8"	1610'	None
		Surface	4691'	4 1/2"	4691'	1684'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

. Load csg w/ mud & set 4 1/2" CIBP @ 4513', cap w/ 2 sks cement. Cut & pull 4 1/2" csg from 1684 . TIH w/ tbg @ 1710' , mix & spot 100 sks  
Class "C" cement @ 14.8 ppg w/ 1.32 yield up to 1510' , Pull up hole @ 690' , mix & spot 50 sks cement up to 490'  
POH w/ tbg & top out 64' - 4' w/ 15 sks cement .

Name of Plugging Contractor: Orr Enterprises, Inc. License #: 33338

Address: P.O. Box 1706 Duncan, OK 73534

Name of Party Responsible for Plugging Fees: EOG Resources, Inc

State of Oklahoma County, Oklahoma, ss.

EOG Resources, Inc. Candy Driscoll (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Candy Driscoll  
(Address) \_\_\_\_\_

SUBSCRIBED and SWORN TO before me this 2<sup>nd</sup> day of February, 20 09  
Kaye Dawn Rockel My Commission Expires: \_\_\_\_\_  
Notary Public

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 04 2009  
CONSERVATION DIVISION  
WICHITA, KS

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

  
KAYE DAWN ROCKEL  
Notary Public  
State of Oklahoma  
Commission # 08010434 Expires 10/24/12

*[Handwritten initials]*