

Orig - State Corp. Comm.
Copy - B. A. Conner - 357 FPB STATE OF KANSAS
Copy - Mary Crump - Okla. STATE CORPORATION COMMISSION
Copy - Well File 200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ellis SEC. 1 TWP. 11 RGE. 16 E/W
Location as in quarters or footage from lines:
S/2 SE/4 SE/4

Lease Owner Phillips Petroleum Company
Lease Name Bowlby-A Well No. D01
Office Address Box 287, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): Disposal
Date Well Completed July 3, 1964
Application for plugging filed March 2, 1983
Plugging commenced April 12, 1983
Plugging completed April 12, 1983
Reason for abandonment of well or producing formation No longer accepting water

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck
Producing formation Arb-LKC Depth to top 3107 bottom 3555 T.D. 3555
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	Water	0	166	8 5/8	166	-0-
Production	Oil & Wtr	0	3464	5 1/2"	3464	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Conn Hallib to 8 5/8" & 5 1/2" csg & inj @10 BPM @ 300 psi. Pmpd 325 sx cmt w/2% gel @ 5 BPM @ 825 psi. ISIP - 800 psi. Pmpd 80 sx in 8 5/8 & 5 1/2" annulus. Max press 200 @ 3 BPM. Cut csg off 4' below GL. Welded on plate. Well P&A 4-12-83

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
Great Bend, Kansas 67530


STATE OF Kansas COUNTY OF Barton, ss.

C. D. Dohrer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C D Dohrer Area Mgr.
Box 287, Great Bend, Ks 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of April, 1983

My Commission expires: February 15, 1984



Velma L. Mog Notary Public.
STATE CORPORATION COMMISSION

4-19-83
APR 19 1983