

15-051-05019-0001

WELL PLUGGING RECORD
K.A.R.-82-3-117

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 051-97607-00
LEASE NAME Gish C
WELL NUMBER #4

TYPE OR PRINT
NOTICE: Fill out completely and return 4290' ft. from S Section Line
to Cons. Div. office within 30 days. 990' ft. from E Section Line

LEASE OPERATOR OXY USA INC.
ADDRESS P.O. Box D, Plainville, KS 67663
PHONE # 785-434-7681 OPERATOR'S LICENSE NO. 5447

Spot Location - - -
SEC 2 TWP 11S RGE 16 or (W)
COUNTY Ellis

Character of Well OIL
(Oil, Gas, D&A, SWD, Input, Water Supply)

Date Well Completed 2-8-584-26-89
Plugging Commenced 9-10-97
Plugging Completed 9-10-97

The plugging proposal was approved on October 22, 1996 (date)
by David Williams (KCC District Agent's Name)

Is ACO-1 filed? ON FILE If not, is well log attached? _____

Producing Formation LKC & Toronto Depth to Top 3171' Bottom 3415' T.D. 3518'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORDS

Formation	Content	From	To	Size	Put in	Pulled out
		5'	248'	8-5/8"	248'	0'
		0'	3518'	5-1/2"	3518'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

*** See back for details ***

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. 1-27-98
Address Russell, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA INC. JAN 27 1998

STATE OF Kansas COUNTY OF Rooks
J.D. Hininger (Employee of Operator) or (Operator) of above-described well, being first duly sworn

on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J.D. Hininger
(Address) P.O. Box D, Plainville, KS 67663

SUBSCRIBED AND SWORN TO before me this 26th day of January 1998

Sheryln Axelson Notary Public

My Commission Expires:
5-20-2000



09/10/97 JOB: Plug and Abandon; CMIC: JD Hininger
P&A - 5 1/2" - Mixed and pumped 40 sks 60/40 cement w/10% gel w/200
lbs. hulls - w/18 sks. gel - 110 sks. cement w/200 lbs. hulls - shut in
w/600 psi. - 8 5/8" - mixed and pumped 25 sks. cement - shut in w/100
psi. - Plugged @ 10:30 A.M. 9/9/97 - State witness Dennis Hamel
MAT \$ 3486; CUM: MAT \$ 3486, TOT \$ 3486;

C#4

RECORDED
STATE OF TEXAS DEPARTMENT OF REVENUE
ADMISSION

JAN 27 1998

RECORDED
STATE OF TEXAS DEPARTMENT OF REVENUE