


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Ellis County. Sec. 3 Twp. 11 Rge. (E) 16 (W)
Location as "NE/CNW%SW%" or footage from lines. S/2 SW SW
Lease Owner Chief Drilling Co., Inc. & Houston Petroleum Co.
Lease Name Pohlman Well No. 1
Office Address P.O. Box 97 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3/10 1960
Application for plugging filed 3/10 1960
Application for plugging approved 3/10 1960
Plugging commenced 3/10 1960
Plugging completed 3/10 1960
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty - Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3600 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	238'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1/3 sack Hulls and Wooden Plug set @ 400'
Mixed 20 sacks cement through drill pipe
1/3 sack hulls and wooden plug set @ 180'
Mixed 15 sacks cement through drill pipe
1/3 sack hulls and wooden plug set @ 40'
Mixed 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
3-16-60
MAR 16 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address P.O. Box 97 - Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
V. Richard Hoover (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. Richard Hoover
P.O. Box 97 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of March 1960

My commission expires May 19, 1960
Norris Taylor Notary Public.



WELL LOG

Chief Drilling Co., Inc. & Houston Petroleum Co.
 P.O. Box 97
 Great Bend, Kansas.

No. 1 Pohlman
 S/2 SW SW Sec. 3-11-16W
 Ellis County, Kansas

Contractor: Chief Drilling Co., Inc.
 Rotary: 0 - 3600'

Commenced: 2-27-60
 Completed: 3-10-60
 D & A

Casing: 8 5/8" set @ 238' with 165 sacks cement, cement circulated.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>	
Shale	0	400	1981 Gr.	
Shale & Sand	400	900	1983 D.F.	
Shale	900	1197	1986 K.B.	
Anhydrite	1197	1230		
Shale & Shells	1230	1565		
Shale	1565	1815		
Lime & Shale	1815	1865	Anhydrite	1197 + 889
Lime	1865	2365	Topeka	2916 - 930
Lime & Shale	2365	2916	Heebner	3156 -1170
Lime	2916	3156	Toronto	3177 -1191
Lime & Shale	3156	3203	Lansing	3202 -1217
Lime	3203	3448	Base Kansas City	3448 -1462
Lime & Shale	3448	3515	Conglomerate	3515 -1529
Conglomerate	3515	3600	Total Depth	3600 -1614
Total Depth		3600		

RECEIVED
 STATE GEOLOGICAL COMMISSION

MAR 16 1960

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the S/2 SW SW of Section 3-11-16W, Ellis County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING COMPANY, INC.

V. Richard Hoover
 V. Richard Hoover - President

Subscribed to and sworn to before me this 12th day of March, 1960.

Norris Taylor
 Norris Taylor, Notary Public

My commission expires May 19, 1960.