

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Ellis SEC. 3 TWP. 11S RGE. 16  W  
Location as in quarters or footage from lines:  
330'S - 990'W of NE Corner


Lease Owner Cities Service Company  
Lease Name Krueger Unit Well No. 401W  
Office Address 209 E. William, Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Service EOR  
Date Well Completed June 5, 1949  
Application for plugging filed August 20, 1982  
Plugging commenced October 12, 1982  
Plugging completed October 14, 1982  
Reason for abandonment of well or producing formation No longer necessary

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck

Producing formation Lsg-KC Depth to top 3205' bottom 3293' T.D. 3560'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	302'	- 0 -
				5 1/2"	3523'	- 0 -

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet for each plug set.

Pumped 35 sacks 50/50 pozmix in 8 5/8" casing. Pressured to 200 psi, shut in. Pumped down 5 1/2" casing - 75 sacks Poxmix plus 35 sacks hulls plus 12 sacks gel plus 70 sacks 50/50 pozmix plus 3 sacks gel plus 1 sack hulls. Then pumped wiper plug and 90 sacks 50/50 pozmix. Pump in 5 1/2" casing 2 sacks hulls, 60 sacks 50/50 pozmix plus 4% gel plus 3% CaCl + 2 sacks hulls in cement. Plug and abandonment completed October 14, 1982.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Halliburton Cementing Service

STATE OF Kansas COUNTY OF Sedgwick, ss.

E. W. Peterman (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

RECEIVED  
STATE CORPORATION COMMISSION  
11-2-82  
NOV 2 1982

(Signature) E. W. Peterman  
800 Sutton Place Bldg, 209 E. William  
Wichita, Kansas (Address) 67202



SUBSCRIBED AND SWORN TO before me this 29 day of October, 19 82

My Commission expires: 2-27-85

Jacqueline Pierce  
Notary Public.  
Jacqueline Pierce