


STATE CORPORATION COMMISSION

Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 211 No. Broadway
 Wichita, Kansas

15-163-02602-0000 *Master Copy*

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Rooks County. Sec. 2 Twp. 10S Rge. 17W (E) (W)

Location as "NE/CNW&SW&" or footage from lines C SW SE
 Lease Owner Davis Bros. - Transit Corporation
 Lease Name Loreg "B" Well No. 1
 Office Address 1516 Liberty Bank Bldg., Oklahoma City, Oklahoma
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed April 7 19 62
 Application for plugging filed April 7 19 62
 Application for plugging approved April 7 19 62
 Plugging commenced April 7 19 62
 Plugging completed April 7 19 62
 Reason for abandonment of well or producing formation No production

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	177'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy drilling mud to 540', set plug, cemented with 20 sacks of cement

Filled hole with heavy drilling mud to 175', set plug, cemented with 15 sacks of cement

Filled hole with heavy drilling mud to 40', set plug, cemented with 10 sacks of cement to bottom of cellar

RECEIVED
 STATE CORPORATION COMMISSION
 4-30-62
 CONSERVATION DIVISION
 WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation
 Address 1516 Liberty Bank Building, Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
L. J. Kruse (employee of owner) or (~~owner~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. J. Kruse

(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of April, 19 62

Paul E. Gubers

Notary Public.

My commission expires January 3, 1966



DRILLER'S WELL LOG

Davis Bros.- Transit Corporation

Loreg "B" # 1 well located in
C SW SE, Section 2-10S-17W,
Rooks County, KansasCommenced: March 30, 1962
Completed: April 7, 1962
Elevation: 2057' K.B.Casing: 8 5/8" @ 180'
Cemented: w/125 sacks

<u>Formation</u>	<u>From</u>	<u>To</u>
Rock	0	30
Sand	30	35
Gray shale	35	150
Blue shale	150	180
Shale	180	660
Shale and shells	660	845
Sand	845	980
Shale red bed	980	1289
Anhydrite	1289	1323
Shale	1323	1900
Lime and shale streaks	1900	2270
Lime w/shale streaks	2270	2810
Lime and shale	2810	2925
Shale	2925	2946
Lime (Topeka)	2946	3025
Lime	3025	3513
Simpson shale	3513	3516
Arbuckle	3516	3520 T. D.

RECEIVED
STATE CORPORATION COMMISSION
APR 25 1962
CONSERVATION DIVISION

I hereby certify the foregoing to be a true and correct Driller's Log
of the formations encountered in the above well.

Subscribed and sworn to before me
this 23rd day of April, 1962

TRANSIT CORPORATION

By L. J. Kinner

My commission expires January 3, 1966

Paul E. Gathers
Notary Public