

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

AMENDED

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

API NUMBER 15-163-20,170-0000

LEASE NAME Melville

WELL NUMBER 1

3630 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 2 TWP. 10SRGE. 17 (X) or (W)

COUNTY Rooks

Date Well Completed 4-24-69

Plugging Commenced 10-17-91

Plugging Completed 10-22-91

LEASE OPERATOR Leben Oil Corporation

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS LICENSE NO. 6566

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? on old form If not, is well log attached? -

Producing Formation Toronto/LKC/Marm. Depth to Top 3188 Bottom 3457 T.D. 3534

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Toronto	Oil	3188	95	8 5/8	211	None
LKC	Oil	3218	3422	5 1/2	3532	1830
Marmaton	Oil	3439	57			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 3110' + 5 sxs cmt. Shot pipe @ 2000' & 1900'. Spotted 225 sxs cmt down 5" casing @ 1200'. POOH w/casing and hooked up to 8 5/8". Spotted 200 sxs 60/40 w/8% gel + 500# hulls. Pressured to 600#. Well P & A'd.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P. O. Box 347, Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so the State Corporation Commission

2-3-92

FEB 03 1992

(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 15th day of Nov., 1991

STATE CORPORATION COMMISSION
WICHITA, KANSAS

Linda M. Muddick
Notary Public

My Commission Expires: 12-23-93