

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15,163-20-236  
-0000  
LEASE NAME Lohreg

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER "B" #1  
SPOT LOCATION NW SE SE  
SEC. 3 TWP. 10 RGE. 17 (E) or (W)

LEASE OPERATOR Kaiser-Francis Oil Company  
ADDRESS Box 666, Ellinwood, Ks. 67526

COUNTY Rooks  
Date Well Completed \_\_\_\_\_  
Plugging Commenced 8-2-85  
Plugging Completed 8-16-85

PHONE # (316-564-2670) OPERATORS LICENSE NO. 6568

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? six

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3507'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	204'	None
				5-1/2"	3505'	1440.35'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 3120' and 5 sacks cement. Shot casing at 2500', 2000' and 1400'. Laid down 45 joints of 5-1/2" casing. Squeezed well with 2 sacks hulls, 50 sacks cement, 10 sacks gel, 100 sacks cement blended with 3 sacks hulls, 10 sacks gel, released plug and pumped 50 sacks of 60/40 pozmix cement with 10% gel and 3% calicum chloride. Maximum pressure was 500 psi and shut in 350 psi.


Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111  
Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold  
(Address) Box 698, Gr. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 21st day of August, 1985



RECEIVED  
STATE CORPORATION COMMISSION  
Iona M. Leatherman  
Notary Public

My Commission expires: \_\_\_\_\_

AUG 23 1985  
8-23-85

CONSERVATION DIVISION  
Wichita, Kansas

Form CP-4