

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-20,238

LEASE NAME Lohreg - 0000

WELL NUMBER "B" #2

SPOT LOCATION SE SE SE

SEC. 3 TWP. 10 RGE. 17 (E) or (W)

COUNTY Rooks

Date Well Completed _____

Plugging Commenced 8-9-85

Plugging Completed 8-16-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS Box 666, Ellinwood, Ks. 67526

PHONE # (316-564-2670) OPERATORS LICENSE NO. 6568

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Six

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom _____ T.D. 3500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	210'	None
				5-1/2"	3498'	1201.96'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 3110' and 5 sacks cement. Shot casing at 2700', 2000', 1400' and 1200'. Pulled 36 joints of 5-1/2" casing. Squeezed well with 2 sacks hulls, 50 sacks cement, 10 sacks gel, 100 sacks cement blended with 3 sacks hulls, 10 sacks gel, released plug and pumped 50 sacks of 60/40 pozmix cement with 10% gel and 3% calcium chloride. Maximum pressure was 350 psi and shutin 250 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 24 day of August, 1985

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

My Commission expires: _____

RECEIVED
STATE CORPORATION COMMISSION
Wichita, Kansas

8-23-85
AUG 23 1985

Form CP-4

CONSERVATION DIVISION
Wichita, Kansas