

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5123
Name: Pickrell Drilling Company, Inc.
Address 1: 100 S. Main, Suite 505
Address 2: _____
City: Wichita State: KS Zip: 67202 + _____
Contact Person: Jack Gurley
Phone: (316) 262-8427
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
LKC "H" Depth to Top: 4218 Bottom: 4235 T.D. _____
LKC "J" Depth to Top: 4270 Bottom: 4286 T.D. _____
Johnson Depth to Top: 4615 Bottom: 4633 T.D. 4698

API No. 15 - 109-20499 - 0000
Spot Description: SE SW SE NE
SE SW NE Sec. 23 Twp. 11 S. R. 33 East West
2,970 Feet from North South Line of Section
1,650 Feet from East West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Logan
Lease Name: Schwartz "E" Well #: 1
Date Well Completed: 04-05-91
The plugging proposal was approved on: 03-19-09 (Date)
by: Darrel Dipman (KCC District Agent's Name)
Plugging Commenced: 3-19-09
Plugging Completed: 3-19-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
LKC "H"	Oil & Water	RECEIVED APR 30 2009 KCC WICHITA	8 5/8	316	None
LKC "J"	Oil & Water		4 1/2	4697	None
Johnson	Oil & Water			DV tool @ 2613 w/	325 sx. (circ.)

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 75 sx. cement w/ 300# cottonseed hulls, 9 sx. gell spacer, 200 sx. cement. Squeezed to 500#. Shut in at 250#. Mixed and pumped 25 sx. cement in 8 5/8 x 4 1/2 annulus and shut in. Witnessed by Darrel Dipman, KCC Rep. Material used: 277 sx. 60/40 Poz mix, 4% gel, 1/4#/sx. of Flo-Seal, 9 sx. Gel, 300# cottonseed hulls. Job completed 11:30 a.m. 3-19-09.

KCC PRT per CP2/3
mobile Drilling Company Inc

Plugging Contractor License #: N/A 5121 Name: Allied Cementing Company, LLC
Address 1: P.O. Box 27 Address 2: _____
City: Oakley State: Kansas Zip: 67748 + 0027
Phone: (785) 672-3452
Name of Party Responsible for Plugging Fees: Pickrell Drilling Company, Inc.
State of Kansas County, Sedgwick, ss.
Jack Gurley Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jack Gurley

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten signature]