

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Globe Operating, Inc.
Address: P.O.Box 12 Great Bend, KS 67530
Phone: (620) 792 7607 Operator License #: 6170
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 4-8-09 (Date)
by: Richard Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 4019 Bottom: 4022 T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 063-21,367-00-00
Lease Name: Bretton
Well Number: 1-26
Spot Location (QQQQ): NE - NE - SW
2310 Feet from North / South Section Line
2970 Feet from East / West Section Line
Sec. 26 Twp. 15 S. R. 30 East West
County: Gove
Date Well Completed: 1-23-1991
Plugging Commenced: 4-8-09
Plugging Completed: 4-8-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	307	8 5/8		None
		0	4398	5 1/2		None
		Port collar @		2046		


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Down casing, pump 80 sacks cement with 4 sacks hulls, 15 sacks gel spacer, 175 sacks cement with 2 sacks hulls. Shut in @ 500#

RECEIVED
APR 28 2009
KCC WICHITA

Name of Plugging Contractor: H-D Oilfield Service, Inc. License #: 32970
Address: P.O.Box 87 Bazine, KS 67516
Name of Party Responsible for Plugging Fees: Globe Operating, Inc. P.O.Box 12, Great Bend, KS 67530
State of Kansas County, Barton, ss.

Richard Stalcup (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Richard Stalcup
(Address) P.O.Box 12, Great Bend, KS 67530

SUBSCRIBED and SWORN TO before me this 27th day of April, 2009
M. Lynne Wooster My Commission Expires: 4-2-11
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT

JOB LOG

SWIFT Services, Inc.

DATE 4-8-09 PAGE NO. 1

CUSTOMER GLOBE OPERATING INC. WELL NO. 1-26 LEASE BRETTON JOB TYPE PTA TICKET NO. 15794

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) GAL	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1200							O.J LOCATION 8 5/8 = 307' 5 1/2 = 4398' PORT COLLAR = 2046' PERFS = 4019 - 4022
	1220		1 1/2		✓		500	PUMP 5 SKS COMPT - BRASS HEAD - HELD
	1245	6	20		✓			PUMP 75 SKS COMPT W/ 4 SKS HULLS
		6	45		✓			PUMP 15 SKS GEL SPACER
		2	46		✓		1000 ^{max}	PUMP 175 SKS COMPT W/ 2 SKS HULLS
							500	SHUT IN
								WASH TRUCK
								RECEIVED APR 28 2009 KCC WICHITA
	1400							JOB COMPLETE
								THANK YOU WAYNE, BRETT, SCOTT