

15-063-20678-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Gove SEC. 5 TWP. 11 RGE. 27 N W  
Location as in quarters or footage from lines:

Center/NE/SE

		5	⊙

Locate Well  
correctly on above  
Section Platt.

Lease Owner CINCO EXPLORATION COMPANY  
Lease Name Howard Smithson Well No. 1  
Office Address P. O. Box 3723 - Victoria, Texas  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Date Well Completed 06/23/83  
Application for plugging filed 06/28/83  
Plugging commenced 06/23/83  
Plugging completed 06/23/83

Reason for abandonment of well or producing formation DRY

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes - Verbal

Name of Conservation Agent who supervised plugging of this well Mr. Baltazor

Producing formation None Depth to top            bottom            T.D. 4650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put In	Pulled Out
Fresh Water Zone	Water	0'	200'			
				8 5/8"	327	None

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from            feet  
to            feet for each plug set. Hole filled with 9.6#/gallon mud. Set cement  
plugs using 50/50 Poz + 6% gel + 3% CaCl<sub>2</sub> as follows:

- 25 sacks from 2340' to 2260'
- 100 sacks from 1300' to 980'
- 40 sacks from 350' to 220'
- 10 sacks from 40' to surface on hulls
- 10 sacks in rathole
- 10 sacks in mousehole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services #5287

STATE OF TEXAS COUNTY OF VICTORIA, ss.

MELVIN KLOTZMAN

(employee of owner) or ~~owner or operator~~ of

the above-described well, being first duly sworn on oath, says: That I have knowledge  
of the facts, statements, and matters herein contained and the log of the above-described  
well as filed and that the same are true and correct. So help me God.

MELVIN KLOTZMAN

(Signature)

P. O. Box 3723-Victoria, TX 77903  
(Address)

SUBSCRIBED AND SWORN TO before me this 28<sup>th</sup> day of June, 19 83

STATE CORPORATION COMMISSION

JUN 30 1983  
6-30-1983

CONSERVATION DIVISION  
Wichita, Kansas

My Commission Expires: 2/06/85

Betty Jean Davis