

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
March 2009
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

OPERATOR: License #: 3273
 Name: Herman L. Loeb LLC
 Address 1: P.O. Box 838
 Address 2: _____
 City: Lawrenceville State: IL Zip: 62439 + _____
 Contact Person: George Payne
 Phone: (812) 453-0385
 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 4876' Bottom: 4896' T.D. 4896'
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 15-097-30029 - 00-00
 Spot Description: 660N-660W from SE corner KCCPKT
C SE SE 1/4 Twp. 27 S. R. 20 East West
660 Feet from North / South Line of Section
660 Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: Kiowa
 Lease Name: Charles Einsel Well #: 2
 Date Well Completed: 1965
 The plugging proposal was approved on: 04/23/2009 (Date)
 by: Steve Durant (KCC District Agent's Name)
 Plugging Commenced: 4/23/2009
 Plugging Completed: 4/27/2009

*KCC PKT
Per 05/2/09*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8 5/8"	595'	0
			4 1/2"	4896'	625'

**RECEIVED
APR 30 2009
KCC WICHITA**

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tbg is parted @ 1527', csg is parted @ 625'. Perf @ 1300' w/ 4 holes. 4/24/2009 Ran tbg to 1497' pump 175 sxs 60/40 4% and let cement set up over weekend. 4/27/2009 Ran tbg and tag bottom @ 675'. Land tbg @ 625'. Mix and pump 200 sxs 60/40 4% and circ cement to surface thru 8 5/8". RDMO

Plugging Contractor License #: 5105 Name: Clarke Corporation Inc.
 Address 1: 107 W. Fowler Address 2: _____
 City: Medicine Lodge State: KS Zip: 67104 + _____
 Phone: (620) 886-5665
 Name of Party Responsible for Plugging Fees: Herman L. Loeb LLC
 State of KS County, Kiowa, ss.
Alan Vratil Employee of Operator or Operator on above-described well,
 (Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: *Alan Vratil*

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT