

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

15-167-06145-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 10-33

LOCATION NE-NE-NE

SEC. 17 TWP. 11 RGE. 15W

Dry Hole _____ Abandoned Oil Well *** Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease American Investment

Operator R. P. Nixon Address 754 E. Wichita, Ave.
Russell, Kansas.

Field _____ County Russell

Total Depth 3405' Feet. P.B.TD. 3278'

Plugging Contractor Arnett Casing Pulling Company.

Plugging Contractor's License No. 265

Address Hoisington, Kansas.

(Describe Briefly the manner in which the well was plugged)

Surface pipe - 8 5/8" @ 1012' c.w.c.

4 1/2" set @ 3404' cem. 200 sx. Perforated from 3014' to 3016'.

Sand back to 3000' & 4 sx. cem. with dump bailer. Shot 4 1/2" off @ 2490'
and pulled same. Filled hole with heavy mud to 300' from top, set plug,
rock bridge and 20 sx. cem. with dump bailer. Mud to 35' from top, set
plug, rock bridge and 10 sx. cem. to base of cellar.

Victor Lyford
District Conservation Agent

Date 5-27-57

RECEIVED
STATE CORPORATION COMMISSION

MAY 29 1957
05-29-1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 17 T. 11 R. 15W
BOOK PAGE 10 LINE 33