

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-145-20,629-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name J. A. Allison

Complete Address 300 W. Douglas - S. 305 - Wichita, KS 67202

Lease Name Rozak Well No. #1

Location NE-NE-SF Sec. 15 Twp. 11 Rge. 25 (East) (West)

County Trigo Total Depth 4070'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing

Address Chase, Kansas License No. 683

Operation Completed: Hour: 3:00pm Day: 29 Month: 7 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" @ 271' w/165sx - 5 1/2" @ 4065' w/150sx
Top Reqs 3857-60' - Cast plug w/5sx emt. @ 3800'
Recovered 1305' of 5 1/2" casing. Ordered 140sx 50% pzgr mix
6% gel - 3% cc - 28 gel - 6 hulls + 8 5/8" plug; pmpd in
5 hulls -> 14 gel -> 1 hull -> 50 cmt (nipple on head broke - lost
50 sx emt. on bleed-back - reorder 50 more sx - repair head)
pmpd in 70 sx emt. -> 14 gel -> 70 cmt. Shut-in PSI 100#

Amount of Surface Casing: 271' (Sun)

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
AUG 02 1982
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 8-11-82
INV. NO. 876-W

Signed: _____
Conservation Division Agent

DBB