

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-167-21,867 <sup>00-00</sup>

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Ivan Holt

Complete Address Box 401, Russell, Kansas 67665

Lease Name Veh Well No. #1

Location SE SE NE Sec. 17 Twp. 11 Rge. 15 (East) (West)

County Russell Total Depth 3530'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling Company

Address 1720 Kansas State Bank Bldg, Wichita, Kansas 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 12:00PM Day: 19th Month: Jan. Year: 19 82

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8"-258' s.p. cuc. w/165 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.  
with

Spot/drill stem with heavy mud between all plugs.

1st plug @ 750' w/70 sacks cement

2nd plug @ 250' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate with 10 sacks of cement in rat hole.

Amount of Surface Casing: 258' of 8 5/8".

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I was on location 4-14S-15W, supervising pipe pulling and plugging of  
said well on that location.

Signed: [Signature]  
Conservation Division Agent

INVOICED  
2582 RECEIVED  
9258-W STATE CORPORATION COMMISSION  
JAN 25 1982  
01-25-1982  
CONSERVATION DIVISION  
Wichita, Kansas