

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 20 1974  
03-20-1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-195-20265-00-00

Operator's Full Name Benjamin J. Tepper & Joe Katz db/a Katz Oil a/c,

Complete Address 420 South Dixie, Coral Gables, Florida.

Lease Name Shearer Well No. 1

Location SW-SE-SW Sec. 13 Twp. 11 Rge. (E) (W) 25

County Trego Total Depth 3989'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.     

Operation Completed: Hour 8:30 AM Day 16 Month 3 Year 1974

The above well was plugged as follows:

239'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota Section @ 800'.

Circulated hole with heavy mud. Pulled DP to 1025' and displaced 110 Cu. Ft. cement  
thru DP from 1025' to 700'. Pulled DP to 250' and displaced 30 Cu. Ft. cement thru  
DP from 250' to 175'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 3/20/74  
INV. NO. 8774-W

Signed: M. L. Nichols  
Well Plugging Supervisor