

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-195-20166-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1970
CONSERVATION DIVISION
Wichita, Kansas
09-23-1970

Operator's Full Name John O. Farmer, Incorporated,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Ziegler Well No. 2 1

Location NE-NE-SE Sec. 17 Twp. 11 Rge. (E) (W) 25

County Trego Total Depth 4016'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated _____

Plugging Contractor Above

Address _____ License No. _____

Operation Completed: Hour 2:15 AM Day 20 Month 9 Year 1970

The above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 875'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 100 Sx. cement thru
DP from 1100' to 775'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 9-23-70
INV. NO. 2579-W