

LEASE NAME Porter #1

WELL NUMBER _____

SPOT LOCATION SW/4

SEC. 17 TWP. 11S RGE. 15W (E) or (W)

COUNTY Russell

Date Well Completed _____

Plugging Commenced 3/7/85

Plugging Completed 3/11/85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Kelso Casing Pulling bought f/ R & D Enterprises

ADDRESS Box 26, RR 1, Paradise, Ks. 67658

PHONE # (913) 998-4461 OPERATORS LICENSE NO. _____

Character of Well _____
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3943'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1048'	none
				5 1/2"	3943'	2313'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set. Well was never completed.

Bottom was already plugged off. Shot pipe at 2522', & 2313'. Pulled 57 joints. Plugged well with 4 hulls, 25 cement, 12 gel, 40 cement, 3 gel, 1 hull, 8 5/8 plug, & 100 sacks cement (50/50 poz 4% gel 3% c.c.)

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

RECEIVED
 STATE CORPORATION COMMISSION


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 11th day of March, 19 85



Irene Hoover
 Notary Public

My Commission expires: _____



**MICRO-SEISMOGRAM®
LOG-CASED HOLE**

COMPANY	COMPANY <u>AMERICAN LIGHT INC.</u>
	WELL <u>PORTER #1</u>
	FIELD _____
	COUNTY <u>RUSSELL</u> STATE <u>KANSAS</u>
WELL	Location <u>SU 1/4</u>
FIELD	
County	
State	
	Sec. <u>17</u> Twp. <u>10</u> Rge. <u>15</u>

Permanent Datum GROUND LEVEL Elev. N/A Elev. N/A
 Log Measured From 0' Ft. Above Perm. Datum
 Drilling Measured From KELLY BUSHING N/A

Run No.	<u>ONE</u>
Date & Time Survey	<u>3-25-82</u>
Date & Time Cementing	<u>N/A</u>
Type Cementing Operation	<u>PRIMARY</u>
Depth Driller	<u>N/A</u>
Depth Welex	<u>3905</u>
Logged Interval	<u>3900 to 2100</u>
Casing Driller	<u>5 1/2" N/A</u>
Float Collar - DV Tool	
Squeeze Depth	
Amount & Type Cement	<u>N/A</u>
Amount & Type Admix	<u>N/A</u>
Type Fluid in Hole	<u>WATER</u>
Fluid Level	<u>750'</u>
Salinity PPM Cl	
Weight lb/gal--Vis	
Approx. Logged Cem. Top	<u>2341</u>
Calculated Cement Top	
Max. Hole Temperature	<u>101°</u>
Tool No	<u>591-304</u>
Spacing Recorded	<u>4'</u>
Equipment - Location	<u>2874 17HY5</u>
Recorded by	<u>R. IJES</u>
Witnessed by	<u>MR. WJN 2METH</u>

RECEIVED
STATE CORPORATION COMMISSION

MAR 07 1985

COMPTON TOOL & DIE CO.
VICTORVILLE, CALIF.