

15-195-21128-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Trego SEC. 16 TWP. 11S RGE. 25W E/W  
Location as in quarters or footage from lines:  
NW SE SW


Locate Well  
correctly on above  
Section Platt.

Lease Owner K & E Petroleum, Inc.  
Lease Name NEWMAN Well No. 1  
Office Address 300 Hardage Center, 100 S. Main, Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed December 28, 1982  
Application for plugging filed December 28, 1982  
Plugging commenced December 28, 1982  
Plugging completed December 28, 1982  
Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Dennis Hamil

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4031'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Set 1st plug @ 2050' with 20 sx.  
Set 2nd plug @ 1050' with 100 sx.  
Set 3rd plug @ 335' with 40 sx.  
Set 4th plug @ 40' Sol. Bridge with 10 sx.  
10 sx. in Rathole. 50-50 posmix, 6% gel, 2% c.c.  
Job complete @ 4:30 p.m., 12/28/82.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.  
801 Union Center, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack L. Partridge, Vice Pres. (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, KS 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of January, 19 83

My Commission expires: 7-13-85

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 06 1983  
01-06-1983  
Wichita, Kansas  
NOTARY PUBLIC  
STATE OF KANSAS  
ETH C. TERRY



# K & E PETROLEUM, INC.

HARDAGE CENTER, SUITE 300

100 SOUTH MAIN

WICHITA, KANSAS 67202

RECEIVED  
STATE REGULATION COMMISSION TELEPHONE  
316/264-4301

1981 KANSAS EXPLORATION PROGRAM  
Prospect 11-25-16

15-195-21128-00-00102-08-1983  
FEB 8 1983  
INSPECTION DIVISION  
Wichita, Kansas

## WELL HISTORY

Operator: K & E Petroleum, Inc.  
Contractor: Abercrombie Drilling  
Geologist: Joe Baker

Lease/Well No.: Newman #1  
Location: 35' East of C NW SE SW  
Section 16-T11S-R25W  
Trego County, KS  
Elevation: 2435' G.L.  
2440' K.B.

Note: Location moved 35' east because of surface terrain.

	Formation	SAMPLE TOPS:		LOG TOPS:	
		Depth	Subsea	Depth	Subsea
12/20/82 M.I.R.R. (Rig #7)					
12/21/82 Depth: 329'. Operation: W.O.C. Well spudded 4:15 P.M., 12/20/82. Drilled 329' of 12 1/2" hole. Ran 8 jts., 20#, new, 8 5/8" casing; set @ 328' and cemented w/225 sx. common (2% gel, 3% C.C.). Plug down @ 1:00 A.M. 12/21/82. Cement circulated.	Anhydrite	2021'	+419'		
	Base Anhy.	2060'	+380'		
	Heebner	3726'	-1286'		
	Toronto	3748'	-1308'		
	Lansing	3764'	-1324'		
	BKC	4018'	-1578'		
	T.D.	4031'	-1591'		
12/22/82 Depth: 2477'. Operation: Drilling. Mud; wt. 9.3, vis. 28. Deviation: 3/4° @ 2035'. ECDC \$26,029.					
12/23/82 Depth: 3240'. Operation: Drilling. Mud; wt. 9.3, vis. 29. Deviation: 1° @ 3570'. ECDC \$33,283.					
12/24/82 Depth: 3600'. Operation: Shut down over Christmas. ECDC \$36,413.					
12/25/82 Shut down.					
12/26/82 Shut down.					
12/27/82 Depth: 3846'. Operation: Drilling. Mud; wt. 9.3, vis. 40, WL 11.4. ECDC \$38,881.					
12/28/82 R.T.D. 4031'. Operation: Laying down drill pipe and preparing to P & A. Mud; wt. 9.3, vis. 40, WL 11.4. No electric log run. Drill pipe strap at 4031'; 0.06' long to board. ECDC \$42,241.					
12/29/82 Plugging completed @ 4:30 P.M., 12/28/82 E.C.D.C. \$44,791. Final report.					

Key Well: D. R. Lauck Drilling Co.  
Ziegler #1  
SE SE SE  
Section 17-T11S-R25W  
Trego Co., Kansas  
(D & A)

Anhydrite	+428
Heebner	-1272
Toronto	-1296
Lansing	-1311
BKC	-1562
RTD	-1584