


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-195-00337-00-00

WELL PLUGGING RECORD

Trego County, Sec. 13 Twp. 11 Rge. 25 (E) (W)

Location as "NE/CNW/SE/SW" or footage from lines NE NE NE/4
Lease Owner M. B. Armer
Lease Name Anna Brown Well No. 1
Office Address 710 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed Dec. 23, 19 55
Application for plugging filed Dec. 23, 19 55
Application for plugging approved Dec. 23, 19 55
Plugging commenced Dec. 23, 19 55
Plugging completed Dec. 23, 19 55
Reason for abandonment of well or producing formation dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4560 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PULL IN	PULLED OUT
				8-5/8"	238	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Circulated hole with heavy mud, set cementing plug at 220 ft.
1/2 sacks hulls and 15 sacks cement. Mudded to 40 ft. set cementing plug, 1/2 sack hulls and 10 sacks cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JAN 3 1956
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, Inc.
Address 710 Petroleum Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
L. C. Sponenberg (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg
(Address) _____

SUBSCRIBED AND SWORN to before me this 29th day of December 19 55
October 13, 1956
My commission expires _____
Lorraine M. Johnson Notary Public.

Notary Seal: Lorraine M. Johnson, Notary Public, State of Kansas, Commission Expires October 13, 1956

PLUGGING
FILE SEC. 13 T. 11 R. 25
BOOK PAGE 27 LINE 34

RECEIVED
STATE CORPORATION COMMISSION
JAN 3 1956
CONSERVATION DIVISION
Wichita, Kansas


KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15-195-00337-00-00
 SEC. 13 T. 11 R. 25 W
 LOC. NE NE NE

COMPANY **M. B. Armer**
 FARM **Anna Brown** NO. **1**

TOTAL DEPTH **4560**
 COMM. **12/9/55** COMP. **12/23/55**
 SHOT OR TREATED
 CONTRACTOR **H-30, Inc.**
 ISSUED

COUNTY **Trego**
 KANSAS



CASING
 20 10
 15 8 **238**
 12 6
 13 5

ELEVATION **2387 KB**
 PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface clay and sand streaks	125
Shale & shells	238
Blue shale & Shells	550
Shale	955
Shale & sand streaks	1235
Sand	1350
Shale & Shells	1540
Sand	1750
Shale, shells & Red Bed	1985
Shale	2000
Anhydrite	2040
Shale & Shells	2475
Shale & Lime shells	2525
Shale & Lime	3680
Lime	3700
Shale & Lime	3769
Lime	3900
Lime & Shale	4326
Shale & Lime, Cherty	4368
Lime & Chert	4392
Shale & Lime	4500
Shale, Lime & Chert	4560

FORMATION TOPS

Howard	3466
Topeka	3515
Heebner	3703
Toronto	3724
Lansing-Kansas City	3740
Base Kansas City	3982
Marmaton	4007
Cherokee	4181
Cherty Conglomerate	4272
Mississippi	4338
Gilmore City	4389
Viola	4470
Arbuckle	4522
Total Depth	4560

PLUGGING
 FILE SEC 13 T 11 R 25w
 BOOK PAGE 29 LINE 34

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

M. B. ARMER

RECEIVED BY *L.C. Spruery*
 STATE CORRELATION COMMISSION

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

JAN 3 - 1955
 01-03-1955
 DIVISION
 Wichita, Kansas

Subscribed and sworn to before me, a notary public, in and for said County and State this 28th day of December, 1955.

My commission expires Oct. 13, 1956 *Lorraine M. Johnson*
 Notary Public