

15-063-21435-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-063-21,435

LEASE NAME Hazelton

WELL NUMBER 3

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

330 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 12 TWP. 11S RGE. 31 (E/W) (N/S)

COUNTY Gove

LEASE OPERATOR Petex, Inc.

ADDRESS 1610 E. Sunshine, Springfield, MO 65804

PHONE# (417) -887-1225 OPERATORS LICENSE NO. 8541

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 6/4/92

Plugging Commenced 6/4/92

Plugging Completed 6/4/92

The plugging proposal was approved on 6-4-92 (date)

by Gib Scheck (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 4630'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	213'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 4630'-2500' 40 sks cement @ 300'  
 25 sks cement @ 2500' 10 sks cement @ 40'  
 100 sks cement @ 1500' 15 sks in rathole  
 60 sks cement @ 1000'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 0750

Address P. O. Box 506, Russell, KS 67665-0506

RECEIVED  
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petex, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

JUN 8 1992  
6-8-1992  
CONSERVATION DIVISION  
Wichita, Kansas

Kyle B. Branum (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
Kyle B. Branum

(Address) P.O. Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 5th day of June, 19 92

GLEND A. R. TIFFIN  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXPIRES 2-6-96

[Signature]  
Glenda R. Tiffin, Notary Public

## EMPHASIS OIL OPERATIONS

P. O. BOX 506  
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Petex, Inc.  
1610 E. Sunshine  
Springfield, MO 65804

CONTRACTOR: Emphasis Oil Operations  
Box 506  
Russell, KS 67665

LEASE: Hazelton WELL #3

LOCATION: NE NW NW  
Section 12-11S-31W  
Gove County, Kansas

LOGGERS TOTAL DEPTH: 4636'

ROTARY TOTAL DEPTH: 4630'

COMMENCED: 5/27/92

CASING: 8-5/8" @ 213' w/140 sks cement

ELEVATION: 2964' K.B.

COMPLETED: 6/4/92

STATUS: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)


Sand & Soil	69'	Lime	3860'
Sand & Shale	347'	Lime & Shale	4279'
Anhydrite	2500'	Lime	4400'
Shale	2527'	Mississippi	4620'
Sand & Shale	2721'	R.T.D.	4630'
Shale	3200'		

STATE OF KANSAS )  
                          ) ss  
COUNTY OF RUSSELL)

RECEIVED  
STATE CORPORATION COMMISSION  
6-8-1992  
JUN 8 1992


CONSERVATION DIVISION  
Wichita, Kansas


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

  
Kyle B. Branum

Subscribed and sworn to before me on June 5, 1992.

My commission expires: February 6, 1996.



  
Glenda R. Tiffin, Notary Public