

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-063-21146-00-01

API NUMBER 15-063-21,146

LEASE NAME Lockwood

WELL NUMBER 1

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 11 TWP. 11 RGE. 31 ~~W~~ or (W)

COUNTY Gove

Date Well Completed 5-26-93

Plugging Commenced 5-26-93

Plugging Completed 5-26-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Castle Resources, Inc.

ADDRESS 1200 E. 27th., Suite 'C', Hays, KS 67601

PHONE# (913) 625-5155 OPERATORS LICENSE NO. 9860

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-3-93 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? Enclosed If not, is well log attached? _____

Producing Formation Lansing Depth to Top 4014 Bottom 4294 T.D. 4428 PBTD

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Lansing</u>	<u>Oil</u>	<u>4014</u>	<u>4294</u>	<u>4 1/2"</u>	<u>4498'</u>	<u>-0-</u>
<u>Pawnee</u>	<u>Oil</u>	<u>4417</u>	<u>4483</u>			
<u>Fort Scott</u>	<u>Oil</u>	<u>4483</u>	<u>4510</u>			
<u>Mississippi</u>	<u>Oil</u>	<u>4588</u>	<u>TD</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Dug out cellar to expose Braden Head and Surface Casing. Pumped 4 sks 60/40 Poz 10% Gel and pressured annulus to 300 psi. Mixed 283 sks. 60/40 Poz. 10% Gel with 250 lbs. Cotton Seed Hulls and filled production casing from TD to Surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. NA

Address Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Castle Resources, Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Terry Williamson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry Williamson

(Address) 1200 E. 27th, Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 14th day of June



Chris Schumacher
Notary Public

My Commission Expires: 5-8-96

Form CP-4
Revised 05-88

RECEIVED

JUN 16 1993

6-16-1993

CONSERVATION DIVISION
Wichita, Kansas