

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Rocks _____

County. Sec. 5 Twp. 10 Rge. 17 (E) (W)

Location as "NE/CNWxSWx" or footage from lines SE/4 NE/4 NE/4

Lease Owner Francis Raymond

Lease Name Dinkel Well No. 1

Office Address 204-A Insurance Building, Wichita

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-4 1953

Application for plugging filed 9-4 1953

Application for plugging approved 9-4 1953

Plugging commenced 9-4 1953


Plugging completed 9-4 1953

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

NORTH



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3604 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1365	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 300' - pushed wooden plug and hulls to 300'
Run 15 sacks cement through drill pipe - filled hole to 40' with
mud and set wooden plug and hulls - run 10 sacks cement filling
hole to cellar floor - cut off surface pipe below plow depth.

RECEIVED
STATE CORPORATION COMMISSION
9-9-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Salina Drilling Corporation, Inc.

Address 801 North 10th Street, Salina, Kansas.

STATE OF Kansas, COUNTY OF Saline, ss.

Elmer Rider (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Elmer Rider

(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of September 1953

My commission expires 5-2-56

[Signature]
Notary Public.

PLUGGING
FILE SEC 5 T 10 R 17W
BOOK PAGE 129 LINE 18

ROTARY DRILLER'S LOG

Dinkel #1

SE NE NE Sec. 5, Twp. 10 S.
R 17 W, Rocks County, Ks.

Elevation: 2099 K B

Casing Record: 1365'-8 5/8" -650
sacks Pozmix-circulated

OPERATOR : Francis M. Raymond
204-A Insurance Building
Wichita 2, Kansas.

Contractor:
Salina Drilling Corp., Inc.
Box #566, Salina, Kansas.

Well Commenced:
8-24-53

Geologist:
Dean Jirrels,
Wichita, Kansas.

Well Completed: 9-4-53

FIGURES INDICATE BOTTOM OF FORMATIONS-KB

Cellar, Base, Rotary Table	8	Sand Hard	2035
Clay	40	Lime-Shale	2130
Sand	80	Lime	2250
Shale & Shells	100	Shale & Shells	2285
Sandy Shale	435	Lime & Shale	2980
Shale & Shells	865	Shale	3005
Sand-Shale	1130	Lime	3070
Red Bed-Shale-Shells	1300	Lime-Shale	3525
Iron	1315	Conglomerate	3591
Shale & Shells	1355	Arbuckle	3604
Sand	1410		
Red Bed & Shale	1500		
Shale & Shells	1725		
Shale	2000	Total Depth	3604

FORMATIONS TOPS AS PICKED BY GEOLOGIST

Topeka	3030
Hebner	3222
Lansing	3263
Conglomerate	3525
Simpson	3559
Arbuckle	3591
Total Depth	3604

The above rotary driller's log is complete and correct to the best of my knowledge.

SALINA DRILLING CORPORATION, INC.

Loren J. Hillman
President.

