

API NUMBER 15-063-21404

LEASE NAME Keller

WELL NUMBER 1

3400 Ft. from S Section Line

4520 Ft. from E Section Line

SEC. 19 TWP. 11 RGE. 31 (X) or (Y)

COUNTY Gove

Date Well Completed 11/5/91

Plugging Commenced 6/21/93

Plugging Completed 6/21/93

15-063-21404-00-00

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Bowman Oil Company

ADDRESS Box 17 Codell, Ks 67630

PHONE (913) 434-7202 OPERATORS LICENSE NO. 6931

Character of Well \_\_\_\_\_

(i.e., Gas, O&A, SWD, Input, Water Supply Well)

Plugging proposal was approved on 6/16/93 (date)

Dennis Hamel (KCC District Agent's Name).

ACC-1 filed? Yes if not, is well log attached? \_\_\_\_\_

Producing Formation Marminton Depth to Top 4287 Bottom 4292 T.O. 4610

Give depth and thickness of all water, oil and gas formations.

L. GAS OR WATER RECORDS

CASING RECORD

| Formation | Content     | From | To   | Size  | Put In | Pulled out |
|-----------|-------------|------|------|-------|--------|------------|
| Marminton | oil & Water | 4287 | 4300 | 8 5/8 | 257    | -0-        |
|           |             |      |      | 1 1/2 | 4610   | -0-        |
|           |             |      |      |       |        |            |
|           |             |      |      |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material is used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet. 25 sacks cement with hulls from 4600 to 3800, 9 sack of Jel and 50 sacks of cement to 2450, 50 sacks of cement to 850 and 25 sacks from there to surface,

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address Box 31 Russell, Ks 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bowman Oil Company

STATE OF Kansas COUNTY OF Rooks, ss.

Louis D. Bowman

(Employee of Operator or Plugging Contractor)

do hereby describe well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Louis D. Bowman

(Address) Box 37 Codell, Ks 67630

SUBSCRIBED AND SWORN TO before me this 8 day of OCTOBER, 19 93

Vesta J. Russell  
 Notary Public

My Commission Expires: 7-17-96

