

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-063-20748-00-00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

API NUMBER 15-063-20,748

LEASE NAME Wieland

WELL NUMBER 1

SPOT LOCATION SW NE NW

SEC. 21 TWP. 11 RGE. 31 ~~W~~ (W)

COUNTY Gove

Date Well Completed 5-18-84

Plugging Commenced 5-18-84

Plugging Completed 5-18-84

LEASE OPERATOR Viking Resources

ADDRESS 217 E. William Wichita, Ks. 67202

PHONE # (316) 262-2502 OPERATORS LICENSE NO. 5011

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation N/A Depth to top _____ bottom _____ T.D. 4630'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	261'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Circ. 30 min. @ 2500', Spotted 25 sx. cement thru drill pipe.

Spotted 100 sx. cement and 1 sk. floreal @ 1670' thru drill pipe.

Spotted 40 sx. cement @ 300' thru drill pipe.

Set bridge plug @ 40', Spotted 10 sx. cement thru drill pipe.

Spotted 15 sx. cement in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address 401 East Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss. STATE CORPORATION COMMISSION


Ernest Sifford (employee of operator) or 6-4-1984 JUN 04 1984

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God. CONSERVATION DIVISION
Wichita, Kansas

(Signature) Ernest Sifford


(Address) 401 E. Douglas, Suite 500
Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 15 day of June, 19 84



David F. Jamis
David F. Jamis, Notary Public

My Commission expires:



15-063-20748-00-00

WHITE

ANDELLISDRILLING, Inc.

DRILLERS LOG

OPERATOR: Viking Resources 217 E. William Wichita, Ks. 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500, Wichita, Ks. 67202

Lease Name Wieland Well No. 1

Sec. 21 T. 11S R. 31W Spot SW NE NW

County Gove State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 261' with 165 sx. 3%cc
2%gel

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4630'

Drilling Commenced 5-9-84 Drilling Completed 5-18-84

Formation	From	To	Tops
Cellar	0	7	
Shale, Sand	7	1263	
Shale, Lime	1263	2475	
Shale	2475	2489	
Anhydrite	2489	2518	
Shale, Lime	2518	4422	
Lime	4422	4630	

RECEIVED
STATE CORPORATION COMMISSION
6-4-1984
JUN 04 1984

CONSERVATION DIVISION
Wichita, Kansas