

15-063-21392-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-063-21,392

LEASE NAME Wieland 'B'

WELL NUMBER #1

1650' Ft. from S Section Line

1220' Ft. from E Section Line

SEC. 21 TWP. 11S RGE. 31 (E) or (W)

COUNTY Gove

Date Well Completed _____

Plugging Commenced 6-9-91

Plugging Completed 6-10-91 (date)

(KCC District Agent's Name).

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A. L. Abercrombie, Inc.

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202

PHONE#(316) 262-1841 OPERATORS LICENSE NO. 5393

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-10-91

by Gib Scheck

Is ACO-1 filed? yes If not, is well log attached _____

Producing Formation Miss. Depth to Top _____ Bottom T.D. 4640'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	297'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Fill w/heavy mud; set 1st plug @ 2500'-2300' w/50 sx; 2nd plug @ 1650'-1250' w/100 sx;
3rd plug @ 350'-190' w/40 sx; 4th plug @ 40'-surface w/wiper plug w/10 sx; Rathole 15 sx
190 sx 60-40 posmix 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A. L. Abercrombie, Inc.


STATE OF Kansas COUNTY OF sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 10th day of July, 19 91



Angela Woodard
Notary Public

My Commission Expires: March 20, 1993