



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dsle Oller of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Oller guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company & Koester Assoc.,

Complete Address: 617 Union Center Building Wichita, Kansas.

Lease Name: Ziegler Well No. 1

Location: CNW-NW Sec. 28 Twp. 11 Rge. (E)(W) 28

County: Gove Total Depth 4515 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Oller was instructed to plug the well as follows:

230'--8 5/8" Surface pipe, cement circulated with 175 Sx.
Top of Dakota Section @ 1050'.

Circulate hole with heavy mud. Pull DP to 1275' and displace 100 Sx.

cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.

Fill DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

H. L. Nichols
Conservation Division Agent