



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

**VERBAL PERMIT FORM**  
 (To Be Filed By Plugging Agent)

**RECEIVED**  
 STATE CORPORATION COMMISSION

12-2-1963  
 DEC 2 1963

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Bill Blackburn of Terrell Drlg & Producing. has this date requested permission to plug the following described well:

Mr. Blackburn guarantees payment of the plugging fee.

Operator's full Name: Fred B. & Phillip Anschutz.

Complete Address: 1521 Wichita Plaza, Wichita, Kansas.

Lease Name: Campbell Well No. 1

Location: CSE-SE Sec. 22 Twp. 11 Rge. (E) (W) 30

County Gove Total Depth 4618 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Blackburn was instructed to plug the well as follows:

22 163' -- 9 5/8" Surface pipe, cement circulated.  
300' -- 8" pipe cemented with 125 Sx.

Circulate hole with heavy mud, set plug @ 550' and 20 Sx. cement.

" " 240' with 1/4 sk. hulls & 30 Sx. cement.  
 " " 40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

*W. L. Nichols*  
 Conservation Division Agent