



15-109-20018-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
1-29-1973
JAN 29 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Clem Burton of Pickrell Drilling Company has this
date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company,

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas.

Lease Name: Swart Well No. D-1

Location: App:-CE/2-SW-NW Sec. 12 Twp. 11 Rge. (E)(W) 32

County: Logan Total Depth 4700' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burton was instructed to plug the well as follows:

257'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1450'.

Circulate hole with heavy mud. Pull DP to 1675' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

R. L. Dickels
Conservation Division Agent