

4-032016

TO: 11-1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - N/A

SW SE SW /4 SEC. 02, 11 S, 32 W
330 feet from S section line
3630 feet from E section line

Operator license# 5131 Lease Hemmert well # 1

Operator: Thunderbird Drilling, Inc. County Logan

Address: P.O. Box 97 Well total depth 4680 feet ¹⁵²¹⁰
Ellinwood, Kansas 67526 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 303 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling, Inc. License# 6050

Address: Chase, Kansas 67524

Company to plug at: Hour: A.M. Day: 1 Month: November Year: 94

Plugging proposal received from: Richard

Company: Kelso Casing Pulling, Inc. Phone:

Were: Order 250 sxs. 60/40 pozmix - 10% gel - 500# hulls
Allied Cement Company.
Order sand and common cement.

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 10 1994
11-10-1994
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:00A.M., Day: 1, Month: November, Year: 94

Actual plugging report: 8 5/8" set @ 303' w/225 sxs. cwc. 4 1/2" set @
4676' w/150 sxs. PBD 4634'. Prod. perf. 4242' - 4643'. Sand back to
4190' w/4 sxs. common cement on sand with bailer. Shots at 2503' -
1545' tight free at 1245'. Mixed and pumped 112 sxs. cement blend w/450#
hulls mixed in to 2500'. Pulled casing to 300' - circulated w/65 sxs.
cement w/50# hulls. Lay down casing - topped off w/10 sxs. Used total
of 187 sxs. cement blend w/500# hulls with Max. P.S.I. 400#. Plug
complete.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did [X] / did not [] observe the plugging. Carl Goodrow

INVOICED

DATE 12-1-94

INV. NO. 41778

(agent)
Form CP-2/3