

4- 020081

TO: 11-22  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API number: 15-109-20,603-0000

NW NE SE /4 SEC. 08, 11 S, 32 W  
2310 feet from S section line  
990 feet from E section line

Operator license# 08541

Lease: Schippers Well # 3

Operator: Petex, Inc.  
Address: 1610 E. Sunshine  
Springfield, Missouri 65804

County: Logan 149.40  
Well total depth 4597 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 $\frac{1}{2}$  Inch @ 280 feet

Aband. oil well \_\_\_\_\_, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A X

Plugging contractor: White & Ellis Drilling, Inc. License# 05420

Address: P.O. Box 48848, Wichita, Kansas 67201-8848

Company to plug at: Hour: \_\_\_\_\_ Day: 22 Month: November Year: 1995

Plugging proposal received from: Judy (secretary)

Company: White & Ellis Drilling, Inc. Phone: 316-263-1102

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2590 feet with	25	sacks	Rat Hole:	15	sacks
2nd plug @ 1670 feet with	100	sacks			
3rd plug @ 330 feet with	40	sacks			
4th plug @ 40 feet with	10	sacks			

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 29 1995  
WICHITA, KANSAS

Plugging Proposal Received by: Ken Kuhn

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 9:00 PM, Day: 22, Month: November, Year: 1995

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2.0 sx celloflake or flowcel.

Remarks: Allied Cementing performed the cement job. (Ticket #3781)

Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Anhy.plug: YES X NO \_\_\_\_\_  
Bottom plug(in place): YES X, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING X. Elevation: 3069 GL

I did [ ] / did not [ X ] observe the plugging.

Ken Kuhn  
(agent)  
Form CP-2/3

DATE: 11-30-95  
INV. NO. 44166  
11-22