

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-20682-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 8-11S-32W  
4950 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: SCHIPPERS Well Number: 4  
County: LOGAN Total Vertical Depth: 4625 feet

Operator License No.: 8541  
Operator Name: PETEX, INC.  
Address: 4175 S. FR 193  
ROGERSVILLE, MO 65742

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 270  
Production: Size \_\_\_\_\_ feet: 150.31  
Liner: Size \_\_\_\_\_ feet:

10/10

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/10/00  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: BILL Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 6% gel with 1/4# flo-seal per sack.  
Spot all plugs thru drill pipe with heavy drilling mud between all plugs.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 10/10/2000 4:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug 2607' w/25 sxs. Middle Anhy.  
2nd. Plug 1680' w/100 sxs. Base of Dakota.  
3rd. Plug 320' w/40 sxs. Surface pipe +50'.  
4th. Plug 40' w/10 sxs. 8 5/8" Wiper plug.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

RECEIVED  
STATE CORPORATION COMMISSION  
10-24-2000  
OCT 24 2000

CORPORATION COMMISSION  
WICHITA, KANSAS

Remarks: ALLIED CEMENT COMPANY.

Plugged through: DP

District: 04

Signed Richard Williams  
(TECHNICIAN)

100.  
INVOICED  
DATE 10/24/00  
2001060878

OCT 11 2000