

15-109-20594-00-00

6-150177

10-21

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-109-20,594-00-00

SE SE NE /4 SEC. 9, 11 S, 32 W
2970 feet from S section line
330 feet from E section line

Operator license# 31283 Lease Nickelson well # 1

Operator: Rheem Resources County Logan

Address: Suite 505, 100 South Main Well total depth 4715 feet ^{153.24}
Wichita, Kansas Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 281 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: L. D. Drilling License# 6039

Address: Great Bend, Kansas

Company to plug at: Hour: AM Day: 21 Month: October Year: 1995

Plugging proposal received from: Greg Davidson

Company: L. D. Drilling phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2600 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1670 feet " 100 " Mousehole: sacks

3rd plug @ 320 feet " 25 "

4th plug @ 40 feet " wiper plug & 10sx

Plugging Proposal Received by: Bruce D. Basye

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 9:30 AM, Day: 21, Month: October, Year: 1995

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 1/4# celloflake or flowcel per sack cement.

Remarks: Elevation: 3070 GL, Anhydrite depth: 2590 - 2620 feet

Did not penetrate Arbuckle, cemented by Allied

I did[] / did not[X] observe the plugging.

Bruce Basye
Bruce D. Basye Geologist
(agent)
Form CP-2/3
KANSAS CORPORATION COMMISSION
12-20-1995
DEC 20 1995

INVOICED

DATE 1-4-96
INV. NO. 44367

CONSERVATION DIVISION
WICHITA, KS