

15-109-20578-00-00

4-060641

1-23

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-109-20,578-00-00

S2 NW NW /4 SEC. 09, 11 S, 32 W
4290 feet from S section line
4620 feet from E section line

Operator license# 8541 Lease Nickelson well # 1

Operator: Petex, Inc. County Logan

Address: 1610 E. Sunshine Well total depth 4675 feet ^{151.94}
Springfield, MO 65804 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 257 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Abercrombie Drilling License# 5422

Address: Wichita, Kansas 67201

Company to plug at: Hour: 5:00A.M. Day: 23 Month: January Year: 95

Plugging proposal received from: Tony

Company: Abercrombie Drilling Phone: 316-262-1841

Were: Order 190 sxs. 60/40 posmix - 6% gel - 1/4# floseal per. sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 5:00A.M., Day: 23, Month: January, Year: 95

Actual plugging report:
1st. plug at 2600' w/25 sxs. - Anhydrite 2583' - 2621'.
2nd. plug at 1680' w/100 sxs. - Dakota 1376' -1676'
3rd. plug at 310' w/40 sxs. - Surface pipe to 257'.
4th. plug at 40' w/10 sxs.
Rathole with 15 sxs.

RECEIVED
KANSAS CORPORATION COMMISSION
1-30-1995
JAN 30 1995

Remarks: Allied Cementing
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: 3076 GL

CONSERVATION DIVISION
WICHITA, KS

I did did not[X] observe the plugging.

[Signature]
FBK (agent)

INVOICED
DATE 2-6-95
42172
WIC. (70)