

6 031057

4-7-88 15-109-20108-00-00

API NUMBER 15- 1981

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE, NE, SW, SEC. 12, T 11 S, R 32 W/EX
2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Lease Name Swart Well # 1 B

Operator: Landmark Oil Exp. Inc.

County Logan 151.19

Name & Address 110 S. Main St. 310

Well Total Depth 4652' feet

Wichita Kansas 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 365'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing License Number 6050

Address Chase, Kansas

Company to plug at: Hour: _____ PM Day: 7 Month: 4 Year: 19 88

Plugging proposal received from Ron _____

(company name) Kelso Casing (phone) _____

were: 8 5/8" set @ 365 w/200sx. 4 1/2" set @ 4561'w/ 235 sx. Top perf 4185' order sand
and common cmt. Pull pipe. order 200 sx ATL cement blend 65/35

10% Gel, 2% Dical, 5 sx Hulls. Allied Cement Co.

RECEIVED
STATE CORPORATION COMMISSION
5-17-1988
MAY 17 1988

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:00pm Day: 7 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 4130' w/4 sx common cmt on sand w/bailer.

Six shots recovered 1500' of 4 1/2" casing. Squeezed 8 5/8" w/25 sx cement followed w/175 sx
cement w/5 sx hulls mixed in.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I (did/did not) observe this plugging.

INVOICED

Signed Carl Goodrow
(TECHNICIAN)

DATE 5-19-88

INV. NO. 20755